

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 24 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Earl Dunlap of C - G Drilling Co. has this
 date requested permission to plug the following described well:

Mr. Dunlap guarantees payment of the plugging fee.

Operator's full Name: C - G Drilling Co.

Complete Address: 107 Rule Bldg., Wichita, Kansas

Lease Name: Neill Well No. # 1

Location: SW SE SE Sec. 15 Twp. 24 Rge. 14 (E) (W) W

County Stafford Total Depth 4242 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dunlap was instructed to plug the well as follows:

207' of 8 5/8" surface pipe, cement circulated with 225
sacks. Fill hole with mud to 220', 1st cementing plug,
1/2 sack hulls, cement with 20 sacks. Fill hole with mud
to 40', 2nd cementing plug, 1/4 sack hulls, cement with 10
sacks to base cellar. Bridge and cement rat hole with 2
sacks.

Very truly yours,

Arlie Ebling
 Conservation Division Agent