

15-095-30075-0000

Form CP-3  
Rev. 6-26-62

KANSAS

*J*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

6-24-66

RECEIVED  
STATE CORPORATION COMMISSION

JUN 24 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name Van Sickle Well No. # 1

Location C SW NE Sec. 29 Twp. 27 Rge. 7 (E) (W) W

County Kingman Total Depth 4360'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 11:45 PM Day 21st Month June Year 1966

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cemented with 300 sacks. Hole was filled  
with drilling mud to 250', 1st cementing plug, bridged with 1/2 sack of  
hulls and 1 sack of Gel-Mud on fluid at 250', and cemented with 30 sacks,  
through the drill pipe. Hole was filled with drilling mud to 50', bridged  
with 1/2 sack of hulls, and 1 sack of Gel-Mud on fluid at 50', and cemented  
25 sacks to the base of the cellar. Rat and mouse holes bridged and cem-  
ented with 5 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/24/66  
INV. NO. 3459-W

Signed: Archie Elving  
Well Plugging Supervisor