


15-095-30236-0000

Form CP-3
Rev. 6-26-62

 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

12-566
RECEIVED
STATE CORPORATION COMMISSION
DEC 5 1966
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Leben Drilling, Inc.

Complete Address: Box 486 GREAT BEND.
815 Wichita Plaza, Wichita, Kansas

Lease Name Dutton Well No. # 1

Location C NW NE Sec. 21 Twp. 27 Rge. 8 (E) (W) W

County Kingman Total Depth 4445'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A _____ X

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 2:45PM Day 1st Month Dec. Year 1966

The Above well was plugged as follows:

210' of 8 5/8" surface pipe, cement circulated with 275 sacks. Hole
was filled with drilling mud to 200', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 200', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/6/66

INV. NO. 4386-u