

15-095-00460-0000

Form CP-3  
Rev. 6-26-62

*16*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

AUG 15 1963  
8-15-63  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Harvey Rosen

Complete Address: 701 Union Center, Wichita, Kansas

Lease Name Lizzy Keller Well No. # 2

Location NE NW NE Sec. 6 Twp. 27 Rge. 8 (E)    (W) W

County Kingman Total Depth 4315

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X

Other well as hereafter indicated:   

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 2:30PM Day 13th Month August Year 1963

The Above well was plugged as follows:

206' of 8 5/8" surface pipe, cement circulated. 4284' of 4 1/2" long string,  
cemented with 190 sacks. Sanded to 4270', cemented with 3 sacks. Hole  
was bailed down and plug was set at 260', 10' rock bridge, cemented  
with 25 sacks. Filled hole with mud to 40', 10' rock bridge, cemented  
with 10 sacks to base cellar.

3385' of 4 1/2" long string was recovered from the hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 8/15/63  
INV. NO. 9583-W