

15-095-01241-0000

Form CP-3
Rev. 6-26-62

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

6-3-63
RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mack Oil Co.

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name Ankerholz Well No. # 1

Location ~~KINGMAN~~ C SW NE Sec. 6 Twp. 27 Rge. 9 (E) (W) W

County Kingman Total Depth 4370

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Mack Oil Co.

Address: 812 Union Center Bldg., Wichita, Kansas License No.

Operation Completed: Hour 12:30 PM Day 29th Month May Year 1963

The Above well was plugged as follows:

318' of 8 5/8" surface pipe, cement circulated with 400 sacks.

Hole was filled with mud to 240', 1st cementing plug, 1/4 sack hulls, cemented with 27 sacks. Hole was filled with mud to 40', 2nd cementing plug, 1/2 sack hulls, cemented with 10 sacks to base cellar. Rat hole bridged and cemented with 2 sacks.

This cement job was done by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED
Signed: Audie Elving
Well Plugging Supervisor
DATE 6/4/63
INV. NO. 4200-W