

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-173-20,404-0000

LEASE NAME Daley

WELL NUMBER A-1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

Ft. from S Section Line

Ft. from E Section Line
SW SW SE

SEC. 33 TWP 29S RGE. 2W (E) or (W)

LEASE OPERATOR Robinson Oil Company

ADDRESS 300 W. Douglas Suite 737
Wichita, Kansas 67202

COUNTY Sedgwick

PHONE# (316) 262-6734 OPERATORS LICENSE NO. 5038

Date Well Completed

Character of Well Gas

Plugging Commenced 8-10-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-31-87

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #2 Wichita, Kansas

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 3220'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	446'	none
				4-1/2"	3190'	2290'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 2640' and 4 sacks cement. Shot pipe @2352', 2320', 2290', pulled a total of 69 joints of 4-1/2" casing. Set rock-bridge @510' and ran 7 yards of redi-mix cement. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.


Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347
Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 3rd day of Sept., 1987

My Commission Expires:



Notary Public
STATE CORPORATION COMMISSION

SEP 4 1987 Form CP-4
9-4-87 Revised 07-86
CONSERVATION DIVISION
Wichita, Kansas

15-173-20404-0000

DRILLER'S LOG

Robinson Oil Company
 Daley "A" No. 1
 SW SW SE
 Sec. 33-T29S-R2W
 Sedgwick County, Kansas

Commenced: 7-12-81
 Completed: 7-20-81

Surface Casing: 446' of 8-5/8"
 cemented w/225 sx, 3% CC, 2% gel

<u>Formation</u>	<u>Depth</u>
Surface	0 - 450
Shale	450 - 487
Shale & Lime	487 - 710
Shale & Sand	710 - 984
Shale & Lime	984 - 1550
Shale w/sand	1550 - 1771
Shale & Lime	1771 - 2476
Shale & Sand	2476 - 2703
Stalnaker Sand	2703 - 2824
Shale & Lime	2824 - 3060
K.C. Lime	3060 - 3087
Lime & Shale	3087 - 3220 T.D.


I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

R. R. A., Inc.

R. R. Abderhalden
 By: R. R. Abderhalden

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 20th day of July 1981.



RECEIVED
 AUG 10 1981
 CONSERVATION
 WICHITA, KANSAS

Adrian E. May
 Notary Public