

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-025-20438-0000

API NUMBER \_\_\_\_\_

LEASE NAME J.W. Wilson #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION NW NE

SEC. 35TWP. 32SRGE. 23W (E) or (W)

COUNTY Clark

Date Well Completed \_\_\_\_\_

Plugging Commenced 11/9/84

Plugging Completed 11/14/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Plano Petroleum Corp.

ADDRESS P.O. Box 247, Plano Tx. 75074

PHONE # ( ) \_\_\_\_\_ OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4730'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	370'	none
				4 1/2"	4729'	3515'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.  
Pumped bottom with 1 hull & 30 sacks common cement, pushed plug to 4300'. Shot pipe at 3800' & 3515'. Pulled 114 joints of pipe. Plugged well with 3 hulls, 15 gel, 70 cement, 15 gel, 1 hull, & 120 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

11-27-84 RECEIVED STATE CORPORATION COMMISSION


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 26th day of November, 1984



Irene Hoover  
Notary Public

My Commission expires: