

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-21,284-0000

LEASE NAME Bloom

WELL NUMBER 3

4620 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 23 TWP. 32 RGE. 12 (E) or (W)

COUNTY Barber

Date Well Completed 8/82

Plugging Commenced 3/2/94

Plugging Completed 3/4/94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR AGV Corp.

ADDRESS 123 N Main Attica, KS 67009

PHONE# (316) 254-7222 OPERATORS LICENSE NO. 5039

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/1/94 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation shaw Depth to Top 3568' Bottom 3572' T.D. 4870'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
shaw	oil & water	3568'	3572'			
		Surface	479'	8 5/8"	479'	none
		Surface	4870'	5 1/2"	4870'	1915'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set 5 1/2" CIBP @ 3500' - load hole w/ fresh water - 2 sax Common on top of CIBP - Cut csg @ 1915' & Lay down - Pump from surface 300# holls + 10 sax gel + 50 sax + 10 gel + 100# holls + 8 5/8" plug + 125 sax cement - use 60/40 poz + 4% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 3000

Address Attica, KS 67009

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Attica Gas Venture


STATE OF _____ COUNTY OF _____, ss.

Carl W. Durr (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carl W. Durr

(Address) Milton, KS 67106

SUBSCRIBED AND SWORN TO before me this 18th day of March, 1994



Sumner
KS.

Maurice Coultter
 Notary Public

My Commission Expires: April 13th 1996