

15-095-20624-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kingman County, Sec. 24 Twp. 27S Rge. 5 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C SW NW

Lease Owner Robert E. Campbell  
Lease Name Bomholt "A" Well No. 1  
Office Address 260 North Rock Road, Suite 110 Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed September 3 1977  
Application for plugging filed September 3 1977  
Application for plugging approved September 3 1977  
Plugging commenced September 3 1977  
Plugging completed September 3 1977  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin, Great Bend, KS  
Producing formation Depth to top Bottom Total Depth of Well 3814'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	224'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 240 feet. Pumped 35 sacks of cement through drill pipe with pump truck. Pushed plug and  $\frac{1}{2}$  sack hulls to 40' and pumped 12 sacks of cement through drill pipe with pump truck to base of well cellar. Plugged rat hole with 5 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 07 1977  
9-7-77  
CONSERVATION DIVISION  
Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc. 910 Union Center, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
John C. Graves (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves  
910 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of September, 1977

Betty Brandt  
Betty Brandt Notary Public.

My commission expires May 9, 1979

ROTARY DRILLERS' LOG

CONTRACTOR: Graves Drilling Co., Inc.  
910 Union Center  
Wichita, Kansas 67202

DRILLING COMMENCED: 27 Aug. 1977

OPERATOR: Mr. Robert E. Campbell  
260 North Rock Rd. #110  
Wichita, Kansas 67206

DRILLING COMPLETED: 3 Sept. 1977

CASING RECORD: 5 Jts, 224' used 8-5/8"  
cemented with 225 sacks

LOCATION: Bomholt "A" No. 1  
C SW NW  
Section 24-27S-5W  
Kingman County, Kansas

- 0 - 50 Sand
- 50 - 265 Red bed
- 265 - 579 Red bed & shale
- 579 - 1130 Shale
- 1130 - 1415 Shale & lime
- 1415 - 1715 Shale
- 1715 - 2293 Lime & shale
- 2293 - 2609 Shale & lime
- 2609 - 2997 Shale
- 2997 - 3213 Lime & shale
- 3213 - 3364 Shale & lime
- 3364 - 3671 Lime
- 3671 - 3768 Shale
- 3768 - 3780 Chert
- 3780 - 3814 Chert & lime
- 3814 Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 07 1977  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *J. Graves* President

STATE OF KANSAS )  
                          ) SS:  
SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public, this 6th day of September, 1977.

My commission expires: 2 February 1980

*Courtney M. Graves*  
Courtney M. Graves Notary Public

