

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County, Sec. 36 Twp. 24 Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines NW SE NW  
Lease Owner Natural Gas and Oil Company  
Lease Name Kachelman Well No. 3  
Office Address Route #1, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed April 16 19 53  
Application for plugging filed July 21 19 55  
Application for plugging approved July 22 19 55  
Plugging commenced August 1 19 55  
Plugging completed August 7 19 55  
Reason for abandonment of well or producing formation depleted production

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production May 22 19 55  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren Horner  
Producing formation Arbuckle Depth to top 4188 Bottom 4208 Total Depth of Well 4218 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8 5/8"	205'	None
Oil String - Arb.				5 1/2"	421.7'	3544'
				Casing perforated from 4190' to 4212'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled the hole with sand from 4217' to 4170' and ran 5 sacks of cement. Pumped in 85 sacks of cement to surface casing. Plugging completed.

(LOG FOR THIS WELL FILED BY WESTGATE GREENLAND OIL COMPANY)

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
T.C. DAVIS (employee of owner) ~~or owner or operator~~

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T.C. Davis  
Reg. Supt.  
Route #1, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10<sup>th</sup> day of August, 1955

My commission expires January 17, 1959 Jean Grabe Notary Public.

CC: State Corporation Commission  
Shreveport  
Wichita

File  
West Supply

PLUGGING  
SEC 36 T 24 R 14W  
BOOK PAGE 136 LINE 17

RECEIVED  
AUG 11 1955  
CONSERVATION DIVISION  
Wichita, Kansas

## DRILLER'S LOG

COMPANY: Westgate Greenland Oil Company  
 FARM: Kachelman #3, NW ~~NE~~ <sup>SE</sup> NW Sec. 36-24-14W, Stafford County, Ks.  
 Elev. 1947 DF  
 CONTRACTOR: Westgate Drilling Corporation  
 COMMENCED: March 28, 1953, Rotary  
 April 16, 1953, Cardwell  
 COMPLETED: April 12, 1953 - Rotary  
 April 16, 1953 - Cardwell

-----  
 0 to 156 Sand  
 156 to 205 Shale  
 205 to 340 Shale and shells  
 340 to 400 Shale and sand  
 400 to 845 Shale, red bed and shells  
 845 to 875 Anhydrite  
 875 to 1175 Shale and shells  
 1175 to 1850 Shale and shells  
 1850 to 1990 Shale and lime  
 1990 to 2115 Lime  
 2115 to 3628 Lime and shale  
 3628 to 3884 Lime  
 3884 to 4014 Shale and lime  
 4014 to 4140 Viola  
 4140 to 4199 Simpson  
 4199 to 4218 Arbuckle  
 4218 T.D. (RB)

Set 205' of 8 5/8" surface, cemented with  $\frac{Y}{225}$  sx cement &  $\frac{B}{3}$  sx calcium chloride.

Set 5 1/2" casing at 4217' RB, cemented with 75 sx cement.

TOPS: Anhydrite	841	Lansing	3614	Simpson Shale	4147
Heebner	3443	Base KC	3882	Simpson Sand	4161
		Viola	4002	Arbuckle	4188

## DRILL STEM TESTS:

3648-88, open 1 hr, rec. 235 feet muddy salt water, BHP 1220#.  
 3688-3726, open 1 hr, rec. 375' muddy salt water, BHP 1200#.  
 4163-72, open 1 hr, rec. 210' gas, 90' oil and gas cut mud, BHP 1300#.  
 4190-4203, open 1 hr, rec. 550' gas, 585' oil, BHP 1385#  
 4203-13, open 1 hr, rec. 3975' oil, 1440# BHP

CORED 4146 to 4170

SCHLUMBERGER RUN.

PERFORATED 118 shots 4190-4212, filled up 3850 feet oil in 3 hours,  
 swabbed 70 BO in 3 hours, natural.

Filed 25 BOPD Temporary Productivity affidavit as of 4-16-53.

C E R T I F I C A T E

I Don Allen, do hereby certify that the above and foregoing is a true and correct copy of the log of the Kachelman #3 NW SE NW Section 36-24-14W, Stafford County, Kansas as reflected by files of the Westgate-Greenland Oil Company.


S/Don Allen

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 17th day of April, 1953.

S/ Esther Unsell, Notary Public

(SEAL)

My Commission expires



RECEIVED  
 STATE CORPORATION COMMISSION

AUG 25 1953

CONSERVATION DIVISION  
 Wichita, Kansas

C O P Y

## FIELD PURCHASE ORDER

NATURAL GAS AND OIL COMPANY

A DIVISION OF  
MISSISSIPPI RIVER FUEL CORP.

No 10875

At Kt. Bend KsField Order No. \_\_\_\_\_ Date 8-11-55Issued to State Corporation CommissionCity Wichita State KsMaterial to be used for Kachelman #3 - (abandonment)

QUANTITY	SIZE	DESCRIPTION	PRICE
		Plugging Assessment	\$25.00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 12 1955

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FLA SEC. 36 T 24 R 14 W  
BOOK PAGE 136 LINE 17

ISSUED AND RECEIVED BY

Buckles ...

FIELD SUP'T.	GEN. SUP'T.	PUR. AGT.
		<u>(Signature)</u>

## NOTICE TO SELLER:

SEND INVOICE IN DUPLICATE AND ORIGINAL BILL OF LADING TO  
NATURAL GAS AND OIL COMPANY, 366 TEXAS EASTERN BUILDING,  
SHREVEPORT, LA.