


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 36 Twp. 24 Rge. 14 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW/NE/4W
Lease Owner Natural Gas and Oil Corp.
Lease Name Kackelman Well No. #2
Office Address Route 1, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed Yes 19
Application for plugging approved Yes 19
Plugging commenced 9-18 19 57
Plugging completed 9-24 19 57
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R.M. Brundedge
Producing formation Depth to top Bottom Total Depth of Well 4210' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		1,134'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured into T.D. 4210'.
Plugging started 9-18-57. Finished 9-24-57.
Pumped 140 bbls water in hole to kill gas and started plugging back with sand. Sanded back to 4170' and dumped 5 sacks cement.
Set 5 1/2" casing at 1,134'. Worked pipe, shot at 3718'. Mixed and pumped 25 sacks mud and 75 sacks cement. Well completed.

10-9-1957

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 1957

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

J. O. Forbes
Box 221, Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of October, 1957

My commission expires November 8, 1960.

Notary Public.



DRILLER'S LOG

COMPANY: Westgate-Greenland Oil Company
 CONTRACTOR: Westgate Drilling Corporation
 FARM: Kachelman #2, SW NE NW Sec. 36-24S-14W,
 Stafford County, Kansas
 COMMENCED: March 11, 1953, Rotary
 April 1, 1953, Cardwell
 COMPLETED: March 27, 1953, Rotary
 April 2, 1953, Cardwell
 ELEVATION: 1946 DF

0	to	130	Sand
130	to	201	Shale
201	to	500	Shale and red bed
500	to	843	Shale and shells
843	to	870	Anhydrite
870	to	1190	Shale and shells
1190	to	1500	Shale, shells w/salt
1500	to	1800	Shale and shells
1800	to	2045	Lime and shale
2045	to	2085	Lime
2085	to	3250	Lime and shale
3250	to	3351	Lime
3351	to	3471	Lime and shale
3471	to	3522	Lime
3522	to	3618	Shale and lime
3618	to	3915	Lime
3915	to	3995	Shale and lime
3995	to	4023	Shale and chert
4023	to	4150	Lime and chert
4150	to	4167	Simpson sand and shale
4167	to	4173	Simpson
4173	to	4182	Shale
4182	to	4212	Core - Arbuckle
		4212	T.D. - RB

Set 200 feet of 8 5/8" 24# surface pipe. Cemented with 225 sacks cement and 3 sacks calcium chloride.

Set 5 1/2" casing at 4211 (RB). Cemented with 75 sacks cement.

C E R T I F I C A T E

I, Don Allen, do hereby certify that the above and foregoing is a true and correct copy of the log of the Kachelman #2, SW NE NW Section 36-24S-14W, Stafford County, Kansas, as reflected by files of the Westgate-Greenland Oil Company

DON ALLEN/s/

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 6th day of April, 1953.

ESTHER UNSELL/s/

My commission expires May 25, 1953.

PLUGGING

FILE SEC 36 T 24 R 14W
 BOOK PAGE 45 LINE 27

9-14-57
 RECEIVED
 STATE CORPORATION COMMISSION

SEP 14 1957

CONSERVATION DIVISION
 Wichita, Kansas

FIELD PURCHASE ORDER

NATURAL GAS AND OIL COMPANY

A DIVISION OF
MISSISSIPPI RIVER FUEL CORP.

Nº 26909

At P. H. Wood, Dallas

Field Order No. _____, Date 10-8-57

Issued to ADDA & LCC Robinson Commission

City Wichita State Kans

Material to be used for Kachempton #2 AFE 6200

QUANTITY	SIZE	DESCRIPTION	PRICE
		Plugging Assessment	\$ 25. ⁰⁰
		SW-NE-NW - 36-24-14w Stoddard County <i>Mo</i>	

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1937
CONSERVATION DIVISION

PLUGGING
FILE SEC 36 T 24 R 14W
BOOK PAGE 45 LINE 27

RECEIVED
STATE OF TEXAS
SPORTSMAN COMMISSION

067 9 1357

CONSERVATION DIVISION

Wichita, Kan.

ISSUED AND
RECEIVED J

NOTICE TO SELLER:

SEND INVOICE IN DUPLICATE AND ORIGINAL BILL OF LADING TO
NATURAL GAS AND OIL COMPANY, 215 RICHARDS BUILDING,
NEW ORLEANS, LA.

FIELD SUP'T.	GEN. SUP'T.	PUR. AGT.
		<i>(Signature)</i>