


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

STAFFORD County, Sec. 36 Twp. 24 Rge. 14W (E) (W)
NE SE SW

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner SANTA FE PIPE & SUPPLY
Lease Name EAGAN Well No. 2
Office Address P. O. BOX 562 - GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed MARCH 24 19 61
Application for plugging filed NOVEMBER 15 19 63
Application for plugging approved NOVEMBER 18 19 63
Plugging commenced NOVEMBER 17 19 63
Plugging completed NOVEMBER 27 19 63
Reason for abandonment of well or producing formation DEPLETED

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well A. ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4105' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	327'	NONE
				4 1/2"	4104'	3479'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED BACK WITH SAND FROM 4104' TO 4060'.
MIXED AND DUMPED 3 SX OF CEMENT FROM 4024'.
PULLED CASING. MIXED AND PUMPED IN 15 SX OF
GEL MUD. PUT IN PLUG. MIXED AND PUMPED IN 80
SX. OF CEMENT FROM 240' TO BASE OF THE CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

JAN 16 1964

1-16-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor ACE PIPE PULLING COMPANY
Address P. O. BOX 304 - GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (Employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P. O. BOX 562 - GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 15TH day of JANUARY, 19 64

My commission expires JULY 31, 1966

Mary M. Guesnier
Mary M. Guesnier Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company. JAMES W. HERSHBERGER
Farm. Eagan No. 2

SEC. 36 T. 24 R.14W
NE SE SW

Total Depth. 4105'
Comm. 3-14-61 Comp. 3-24-61
Shot or Treated.
Contractor. White & Ellis Drlg.
Issued. 3-17-62

County Stafford
KANSAS



Elevation. 1955'

Production. 122 BOPD

CASING:

8 5/8" 327' cem w/250 sx.
4 1/2" 4104' cem w/50 sx.

Figures Indicate Bottom of Formations.

sand	60
sand & shale	265
shale	350
red rock	855
Anhydrite	885
shale & shells	1050
shale & red rock	1100
shale & shells	1650
shale & Anhydrite	1950
lime & shale stks.	2890
shale & lime stks.	3100
lime & shale stks.	3240
lime	3503
shale	3510
lime & shale	3548
shale	3677
lime	3932
lime & shale	3954
shale	3969
lime & shale	4007
lime	4056
shale, cherty	4105
Total Depth	

TOPS:

Heebner	3503
Toronto (scout)	3523
Kansas City	3677
Brown Lime (scout)	3644
Lansing-Kansas City	3735
Mississippi	4007

RECEIVED
STATE CORPORATION COMMISSION

JAN 16 1964

CONSERVATION DIVISION
Wichita, Kansas