

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford

County. Sec. 36 Twp. 24 Rge. 14 (E) (W)

Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines SE/NE NE NW

Lease Owner Natural Gas and Oil Company

Lease Name Kackelman Well No. #1

Office Address RFD 1, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19 _____

Application for plugging filed Yes 19 _____

Application for plugging approved Yes 19 _____


Plugging commenced 3-20 1957

Plugging completed 4-4 1957

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. R.M. Brundedge

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4234' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,357'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into TD 4234'.
Plugging started 3-20-57. Finished 4-4-57.
Plugged off bottom with sand to 4170' and dumped 5 sacks cement with bailer. Shot 5 1/2" casing at 2,357'. Finished laying down pipe, squeezed well with 25 sacks gel mud and 80 sacks cement. Well completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.

Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of April, 1957.

My commission expires November 8, 1960.

Betty S. Edman
STATE CORPORATION COMMISSION Notary Public.

PLUGGING
FILE SEC 36 T 24 R 14W
BOOK PAGE 148 LINE 3

APR 5 1957
4-9-57
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

COMPANY: Westgate-Greenland Oil Company
 CONTRACTOR: Westgate Drilling Corporation
 FARM: Kachelman #1, NE NE NW 36-24-14W,
 Stafford County, Kansas
 COMMENCED: February 13, 1953 - Rotary
 March 2, 1953 - Cardwell
 COMPLETED: February 28, 1953 - Rotary
 March 5, 1953 - Cardwell
 ELEVATION: 1947 DF

0 to 140	Sand
140 to 211	Shale and shells
211 to 500	Shale, sand and shells
500 to 890	Red bed - shells
890 to 1275	Shale and shells
1275 to 1750	Shale, salt and shells
1750 to 1800	Shale and shells
1800 to 2050	Shale and lime
2050 to 2175	Lime
2175 to 3290	Lime and shale
3290 to 3365	Lime
3365 to 3693	Lime and shale
3693 to 3915	Lime
3915 to 3975	Lime and shale
3975 to 4026	Lime-chert and shale
4026 to 4147	Chert and lime
4147 to 4157	Shale
4157 to 4168	Sand
4168 to 4181	Shale and lime
4181 to 4184	Shale
4184 to 4234	Arbuckle lime
4234	T. D. (RB)

Set 210 feet of 8 5/8" surface 24#. Cemented with 225 sacks cement and 3 sacks calcium chloride.

Set 5 1/2" casing 4233 (RB). Cemented with 75 sacks cement.

C E R T I F I C A T E

I, G. E. Bitler, do hereby certify that the above and foregoing is a true and correct copy of log of the Kachelman #1, NE NE NW Section 36-24-14W, Stafford County, Kansas, as reflected by files of The Westgate-Greenland Oil Company.

G. E. Bitler

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 7th day of March, 1953.

Esther Unsell, Notary Public

My commission expires May 25, 1953.

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING			
FILE	SEC	36 T. 24 R. 14W	
BOOK	PAGE	148	LINE 3