

1 050813

15-025-10028-0000

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Completed 4-20-62

C NW SE, SEC. 35, T 32 S, R 23 W/E

1980 feet from S section line

1980 feet from E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 4058

Lease Name Abell Well # 2

Operator: American Warriors, Inc.

County Clark

Name &amp;

Address P. O. Box 399

Well Total Depth 4760 feet

Garden City, KS 67846

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 526

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor American Warriors, Inc.

License Number 4058

Address P. O. Box 399, Garden City, KS 67846

Company to plug at: Hour: 11:00 am Day: 22 Month: May Year: 19 86

Plugging proposal received from Bill Dailey

(company name) American Warriors (phone) 316-275-9231

were: 5 1/2" at 4759' Perfs at 4667-92'

Squeeze well with 2 sx hulls, 50 sx cement, 15 sx gel, 50 sx cement, 10 sx gel, 50 sx  
cement, 10 sx gel, release 5 1/2" rubber plug and pump 100 sx cement.

Pump 100 sx cement down annulus.

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 2:30 pm Day: 22 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug squeezed well with 2 sx hulls, 50 sx cement, 15 sx gel,

50 sx cement, 10 sx gel, 50 sx cement, 10 sx gel, released 5 1/2" rubber plug and pumped

100 sx cement, 2nd plug pumped 100 sx cement down annulus.

Used 60/40 Pozmix 6% gel by Halliburton

Remarks: No recovery. Maximum pressure 200 psi and shut in 100 psi on 8 5/8"  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JUN 3 1986

INV. NO. 14041

Signed Richard W. Lacy

(TECHNICIAN)

FORM CP-2/3  
Rev. 01-84