

To: 1 040830
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,284-0000
E/2 NW NW, SEC. 23, T 32 S, R 12 W/2
4620 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5039
Operator: AGV Corporation
Name & Address: 123 N. Main
Attica, KS 67009

Lease Name Bloom Well # 3
originally #3 Wiskey Hills
County Barber
Well Total Depth 4872 158.34 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 479

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Shawnee Well Service License Number 30346
Address Attica, KS 67009

Company to plug at: Hour: 3:30 p.m. Day: 4 Month: 3 Year: 19 94

Plugging proposal received from Carl Durr
(company name) Shawnee Well Service (phone) 316-478-2890

vers: 5 1/2" at 4870', CIBP at 3750', Perfs at 3568-3572'
1st plug set CIBP at 3500' and dump 2 sx cement on top,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 4 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3500' and dumped 2 sx cement on top of CIBP through bailer, 3-9-94

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 125 sx cement.

Had to swedge surface pipe at bradenhead-no wiper plug.

Maximum pressure 1000 psi and shut in 700 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1950' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED
did observe this plugging.

DATE 3-14-94

INV. NO. 40091

Signed Stephen J. [Signature] (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAR 09 1994