

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-20377-00-01
Spot: N2NENESW Sec/Twnshp/Rge: 19-34S-43W
2536 feet from S Section Line, 2960 feet from E Section Line
Lease Name: INTERSTATE Well #: A1-19
County: MORTON Total Vertical Depth: 4700 feet

Operator License No.: 5156
Op Name: WHITE, EDGAR W.
Address: 701 VILYMACA ST PO BOX 450
ELKHART, KS 67950

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2670		WITH 2 SX CMT
MSCC		2990		CEMENTED WITH 600 SX CMT
PROD 4.5		4658	0	WITH 475 SX CMT
SURF 8.625		1199		WITH 700 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/02/2016 1:00 PM
Plug Co. License No.: 34199 Plug Co. Name: RAWHIDE WELL SERVICE, LLC
Proposal Rcvd. from: JARED NICKS Company: RAWHIDE WELL SERVICE, LLC Phone: (307) 587-0090

Proposed Plugging Method: SET CIBP @ 2670' WITH 2 SX CMT. RUN TBG TO 1240'-0'.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/03/2016 12:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

3/2/16: SET CIBP @ 2670' WITH 2 SX CMT. RAN TBG TO 1240' & PUMPED 150 SX CMT. CMT DID NOT CIRCULATE. PUMPED 25 SX CMT DOWN THE BACKSIDE.
3/3/16: TAGGED TOC @ 1040'. PRESSURED CASING TO 300 PSI. RAN TBG TO 1040' CIRCULATED TO 0' WITH 75 SX CMT. TOPPED OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4221	4224		
2990			CSG 600 SX TO SURFA
2924	2932		
2801	2809		
2792	2798		
2734	2742		
2720	2780		

Remarks: USED CLASS C CEMENT BY PARTNERS OILFIELD SERVICES.

Plugged through: TBG

District: 01

Signed BW

RECEIVED
MAR - 7 2016
KCC DODGE CITY

JA KCC WICHITA (MANICIAN)
MAR 11 2016
RECEIVED

700
3-17-16
Form CP-2/3