

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-00117-00-00
Spot: SESW Sec/Twnshp/Rge: 7-34S-43W
848 feet from S Section Line, 2971 feet from E Section Line
Lease Name: INTERSTATE B Well #: 1
County: MORTON Total Vertical Depth: 4830 feet

Operator License No.: 5156
Op Name: WHITE, EDGAR W.
Address: 701 VILYMACA ST PO BOX 450
ELKHART, KS 67950

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4700	0	WITH 500 SX CMT
SURF	13.375	529		WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/01/2016 10:00 AM
Plug Co. License No.: 34199 Plug Co. Name: RAWHIDE WELL SERVICE, LLC
Proposal Rcvd. from: STEVE HELM Company: MIDCON CONSULTING Phone: (620) 624-2228

Proposed Plugging Method: PERFORATE AT 1320' WITH 12 SX GEL & 50 SX CMT. 100# HULLS IN LAST 25 SX CMT. PERFORATE AT 570' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2016 5:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

PERFORATE AT 1320' WITH 12 SX GEL & 50 SX CMT. (100# HULLS IN LAST 25 SX CMT). PERFORATE AT 570' WITH 400 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
4336	4344		
3236	3250		
3206	3226		
3180	3190		
3036	3050		
2976	2980		
2960	2966		
2918	2924		
2898	2902		
2858	2862		
2840	2850		
2794	2806		

Remarks: USED 60/40 POZMIX 4% GEL BY PARTNERS OILFIELD SERVICE

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
MAR - 9 2016
KCC DODGE CITY

KCC WICHITA
MAR 11 2016
RECEIVED

200
3-17-16
KMS
Form CP-2/3