

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-05311-00-00
Spot: SEWNESW Sec/Twnshp/Rge: 21-11S-18W
2092 feet from S Section Line, 3596 feet from E Section Line
Lease Name: WASINGER A Well #: 4
County: ELLIS Total Vertical Depth: 3497 feet

Operator License No.: 34559
Op Name: WM KS ENERGY RESOURCES LLC
Address: 1001 FANNIN, STE 4000
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3476		150 SX
SURF	8.625	1243		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/24/2016 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JIM WATTS Company: WM KS ENERGY RESOURCES Phone: (318) 429-2277

Proposed Plugging Method: Ordered 725 sx 60/40 pozmix 4% gel cement and 900 # hulls.
Perfs- Arb- 3484' - 3486'
02/25/2016- Ordered 200 sx 60/40 pozmix 4% gel cement, 14 sx cc and 250 # hulls.
02/26/2016- Ordered 200 sx common w/3% cc.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/26/2016 10:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed at 1200'. Express Well Service ran in hole with tubing to 3399'. Quality rigged to tubing and pumped 155 sx w/300 # hulls mixed in. Pulled tubing to 1837'. Rigged to tubing and pumped 370 sx cement w/300 # hulls. Ran out of cement. Pulled tubing to 1528' and pumped 200 sx cement w/300 # hulls. Cement did not circulate. Shut down at 2:30 pm. Had small traces of cement in water out of 8 5/8" casing.
02/25/2016- Ran in hole and tagged cement at 1528'. Quality rigged to tubing and pumped 50 sx cement w/4% cc and 100 # hulls. Pulled tubing and left set for 1 hour. Ran tubing in hole and tagged at 1528'. Pumped 50 sx cement w/4% cc and 150 # hulls. Pulled tubing. Left set for 1 hour. Ran in hole with tubing and tagged cement at 1528'. Pumped 50 sx cement w/3% cc followed by 50 sx cement.
02/26/2016- Tagged cement at 806'. Pulled tubing to 775'. Rigged to tubing and pumped 80 sx common w/3% cc to circulate cement up 5 1/2" casing. Pulled tubing. Topped off 5 1/2" casing w/5 sx cement. Hole standing full. Rigged to 8 5/8" casing with instant pressure. Blew cement out of hole behind the head.

GPS: 39.07994 -099.32795

Perfs:

Top	Bot	Thru	Comments
3484	3486		

Remarks: QUALITY WELL SERVICE CEMENTING CO TICKET # 3728, 3729 AND 3730.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)
KCC WICHITA

CM

MAR 01 2016

MAR 09 2016

RECEIVED

Form CP-2/3

no 3-17-16