

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-04947-00-00  
Spot: NESESESW Sec/Twnshp/Rge: 21-11S-18W  
375 feet from S Section Line, 2957 feet from E Section Line  
Lease Name: WASINGER A Well #: 3  
County: ELLIS Total Vertical Depth: 3594 feet

Operator License No.: 34559  
Op Name: WM KS ENERGY RESOURCES LLC  
Address: 1001 FANNIN, STE 4000  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3582		150 SX
SURF	8.625	1290		600 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/23/2016 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JIM WATTS Company: WM KS ENERGY RESOURCES LLC Phone: (318) 429-2390

Proposed Plugging Method: Ordered 730 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Open hole from 3582' - 3594'.  
Junk in hole (Tubing) at 2725'  
Casing leaks

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/23/2016 12:50 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Gemini Logging shot 2 perf hole at 1200'. Express Well Service ran in hole and tagged tubing at 2725'. Pulled tubing to 2690'. Quality rigged to tubing and pumped 50 sx neat cement and 50 sx cement w/200 # hulls mixed in. Pulled tubing to 1850'. Quality rigged to tubing and mixed and pumped 200 sx cement w/400 # hulls mixed in to circulate cement up 5 1/2" and 8 5/8" casings. Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 20 sx cement at 100 psi. Cement blew out of 8 5/8" casing.

GPS: 39.07495 -099.32569

Perfs:


Top	Bot	Thru	Comments
3582	3594		

Remarks: QUALITY OILWELL CEMENTING TICKET # 3727

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

KCC WICHITA

MAR 09 2016

RECEIVED

Form CP-2/3

*MO*  
*3-17-16*

MAR 01 2016