

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-21065-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 17-9S-18W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: HILGERS B Well #: 1  
County: ROOKS Total Vertical Depth: 3544 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3542		200 SX
SURF	8.625	316		180 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/24/2016 9:00 AM  
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.  
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Production perforations: 3542' - 3544'.  
DV Tool at 1493' w/550 sx cement.  
Casing leak squeezed from 986' - 1081' w/70 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/24/2016 11:15 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3370' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1600' and pumped 100 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing and topped off 4 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped less than 1/4 bbl. Shut in pressure 300 psi.

GPS: 39.27148N -099.35339W

Perfs:

Top	Bot	Thru	Comments
3542	3544		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1516

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

KCC WICHITA

MAR 11 2016

RECEIVED

MAR 07 2016

Form CP-2/3

*no 3-17-16*