

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-21055-00-01
Spot: SWNWNWNE Sec/Twnshp/Rge: 2-18S-13W
4669 feet from S Section Line, 2524 feet from E Section Line
Lease Name: AKERS Well #: 1
County: BARTON Total Vertical Depth: 3347 feet

Operator License No.: 30886
Op Name: THOMAS, JOHN R. DBA VAMCO OPER
Address: 265 AVENUE K
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3345		150 SX
SURF	8.58	485		250 SX

Well Type: EOR UIC Docket No: E23217.1 Date/Time to Plug: 02/17/2016 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed
Plugging
Method:

Ordered 13 sx gel, 450 sx 60/40 pozmix 4% gel cement and 500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/17/2016 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Well was sanded off to 2837'. Operator was going to pull casing and decided to plug through tubing.
Perforated at 1400', 750' and 450'. Ran tubing to 2800' and pumped 13 sx gel followed by 25 sx cement w/50 # hulls. Pulled tubing to 1400' and pumped 70 sx cement w/200 # hulls. Pulled tubing to 700' Circulated cement to surface on casing w/120 sx cement. Pulled tubing. Tied to casing and circulated cement to surface on surface pipe w/80 sx cement.

GPS: 38.52008 -098.72803

Perfs:

Top	Bot	Thru	Comments
3329	3345		

Remarks: QUALITY WELL SERVICE.

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

KCC WICHITA

MAR 04 2016

RECEIVED

FEB 18 2016

Form CP-2/3

no
3-17-16
CC uic