

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23093-00-00
Spot: NENWSESW Sec/Twnshp/Rge: 34-7S-21W
1010 feet from S Section Line, 1660 feet from W Section Line
Lease Name: STEHNO FARMS Well #: 1
County: GRAHAM Total Vertical Depth: 3635 feet

Operator License No.: 31909
Op Name: STULL OIL LLC
Address: 613 N. 1ST ST PO BOX 307
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3631		150 SX
SURF	8.625	236		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2016 2:00 PM
Plug Co. License No.: 34266 Plug Co. Name: PRAIRIE HAWK WELL SERVICE LLC
Proposal Rcvd. from: JOEL STULL Company: STULL OIL, LLC Phone: (785) 885-4272

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/200 # hulls and 13 sx gel.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2016 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3400' and pumped 13 sx gel followed by 50 sx cement w/50 # hulls. Pulled tubing to 1612' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 582' and pumped 50 sx cement. Circulated cement to the steel pit. POOH. Hooked to 5 1/2" casing and pumped 20 sx cement at 250 psi. Shut in. Hooked to braden head and pumped cement to pressure to 200 psi. Took off the iron of casing and topped off casing.

GPS: 39.39689 -099.65265

Perfs:

Top	Bot	Thru	Comments
3422	3424		
3268	3270		

Remarks: BASIC CEMENTING TICKET # 13016

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

cm

KCC WICHITA

MAR 09 2016

RECEIVED

MAR 01 2016

Form CP-2/3

NO 3-17-16