

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-179-20591-00-01  
Spot: NWSWNE Sec/Twnshp/Rge: 17-9S-26W  
3557 feet from S Section Line, 2389 feet from E Section Line  
Lease Name: MILLS Well #: 17-72  
County: SHERIDAN Total Vertical Depth: 2050 feet

Operator License No.: 5474  
Op Name: NORTHERN LIGHTS OIL COMPANY, LL  
Address: PO BOX 164  
ANDOVER, KS 67002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4081		100 SX
SURF	8.625	284		175 SX

Well Type: SWD UIC Docket No: D20469.0 Date/Time to Plug: 02/22/2016 1:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: ROBERT SUTHERLAND Company: NORTHERN LIGHTS Phone: (316) 733-1515

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
8 5/8" surface casing set at 284' w/175 sx cement.  
4 1/2" production casing set at 4081' w/100 sx cement.  
DV Tool set at 2301 w/400 sx cement.  
TD 4090', PBTD 2050'.  
Perforations: 1905' - 2005'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/22/2016 3:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 1733'. Tubing began contacting fill- up. Contacted district supervisor for instruction. Decision made to plug from 1733'. Pumped 70 sx cement w/200 # hulls. Pulled tubing to 1000' and pumped 70 sx cement w/200 # hulls. Circulated cement to surface. Pulled tubing to surface. Connected to 4 1/2" casing and pumped 15 sx cement. Connected to 8 5/8" surface casing and pumped 5 sx cement. Pressured to 150 psi before head ruptured. Plug complete.

GPS: 39.27237N -100.24597W

Perfs:

Top	Bot	Thru	Comments
1905	2005		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1515

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

KCC WICHITA

MAR 09 2016

RECEIVED

MAR 01 2016

Form CP-2/3

*NO*  
*3-17-16*  
*cc UIC*