

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-04129-00-01  
Spot: NWNESW Sec/Twnshp/Rge: 7-15S-13W  
2303 feet from S Section Line, 3784 feet from E Section Line  
Lease Name: MAAG Well #: 3  
County: RUSSELL Total Vertical Depth: 3310 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3310		100 SX
SURF	8.625	485		225 SX

Well Type: EOR UIC Docket No: E13776.1 Date/Time to Plug: 03/01/2016 7:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: BRENT HOMEIER Company: MAI OIL OPERATIONS, INC. Phone: (785) 445-2353

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/300 # hulls.  
Tubing parted at 732'. Tried washing over and could not get over. Tubing possibly bent over. 2302' of 2 3/8" tubing and R-4 packer left in hole.  
Squeezed at 635' w/400 sx cement.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/01/2016 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Hooked to casing and pumped 50 sx cement and displaced down to 700' at 500 psi. Rigged up and perforated at 731'. Tagged parted tubing at 732'. Ran tubing to 680' and pumped 60 sx cement. POOH. Hooked to casing and pumped 90 sx cement w/150 # hulls. Pressure climbed to 600 psi. Displaced 1/4 BBL and shut in at 350 psi. Dug out braden head and found to be full of cement.

GPS: 38.76125 -098.81256

Perfs:

Top	Bot	Thru	Comments
3232	3236		
3130	3134		
3081	3089		
3066	3068		

Remarks: QUALITY CEMENTING TICKET # 1652

Plugged through: TBG

District: 04

Signed

*Ray A. Dinkel*

(TECHNICIAN)

cm

MAR 07 2016

KCC WICHITA

MAR 11 2016

RECEIVED

Form CP-2/3

*MO 3-17-16 CC WIC*