

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-011-24059-00-00
Spot: S2NWSESE Sec/Twnshp/Rge: 6-24S-22E
960 feet from S Section Line, 990 feet from E Section Line
Lease Name: FOOSE Well #: Z 26-6
County: BOURBON Total Vertical Depth: 722 feet

Operator License No.: 5786
Op Name: MCGOWN DRILLING, INC.
Address: PO BOX K
MOUND CITY, KS 66056

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	683		98 SX
SURF	7	23		6 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/08/2015 12:00 AM
Plug Co. License No.: 31813 Plug Co. Name: BECKER, STEVE A. DBA A & A WELL SERVICE
Proposal Rcvd. from: CHRIS MCGOWN Company: _____ Phone: (913) 795-2259

Proposed Plugging Method: Run 1" to bottom and fill casing with Portland slurry.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 10/08/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:
Ran 1" pipe down the 2.875" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2.875" casing from TD to surface. Pulled the 1" pipe out of the casing and topped the well off with cement. A total of 26 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
648	658		

RECEIVED
KCC DIST # 3
MAR 09 2016
CHANUTE, KS

RD

Remarks:
Plugged through: TBG

District: 03

Signed _____
Received (TECHNICIAN)
KANSAS CORPORATION COMMISSION

MAR 14 2016
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3
NO
3-17-16