

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-20276-00-00  
Spot: NWSW Sec/Twnshp/Rge: 17-21S-33W  
1977 feet from S Section Line, 4602 feet from E Section Line  
Lease Name: WAMPLER Well #: 1  
County: FINNEY Total Vertical Depth: 4725 feet

Operator License No.: 30535  
Op Name: HARTMAN OIL CO., INC.  
Address: 10500 E BERKELEY SQ PKWY STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1175		
CIBP		2500		WITH 2 SX CMT
PROD	4.5	2755	0	WITH 325 SX CMT
SURF	8.625	368		WITH 300 SX CMT

Well Type: GAS UIC Docket No: Date/Time to Plug: 02/16/2016 8:00 AM  
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.  
Proposal Rcvd. from: KENT STRUBE Company: HARTMAN OIL Phone: (620) 786-4161

Proposed Plugging Method: PLUGGIN PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/16/2016 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2500' WITH 2 SX CMT. CIBP @ 1175' TO ISOLATE GLORIETTA CASING LEAK. LOAD & TEST CASING TO 500#. HOLDING. RUN CBL FROM 1170' TO 100'. TOC @ 600'. USABLE WATER IS COVERED. PERFORATE 4 HOLES AT 400'. RUN TBG TO 1160' & CIRCULATE CMT TO SURFACE BOTH INSIDE THE 4 1/2" CASING & THROUGH PERFS AT 400' IN THE 4 1/2" X 8 5/8" ANNULUS USING A TOTAL OF 125 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2560	2570		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed

*Ken Jehlik*  
500

(TECHNICIAN)  
KCC WICHITA

RECEIVED  
FEB 19 2016  
KCC DODGE CITY

MAR 04 2016  
RECEIVED

Form CP-2/3

203-17-16