

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20442-00-00
Spot: NENESWNE Sec/Twnshp/Rge: 15-23S-41W
3945 feet from S Section Line, 1333 feet from E Section Line
Lease Name: HCU Well #: 1531-B
County: HAMILTON Total Vertical Depth: 2724 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2488		
PROD	4.5	2724	0	WITH 600 SX CMT
SURF	8.625	349		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/25/2016 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: LEO Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2016 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2488'. FILL 4 1/2" CASING WITH CMT FROM 2457' TO 0' IN 2 STAGES USING AT TOTAL OF 210 SX CMT. PUMP 20 SX CMT DOWN THE ANNULUS TO 500 PSI. TOP OFF 4 1/2" CASING WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2530	2540		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
SA

(TECHNICIAN)
KCC WICHITA

RECEIVED
MAR - 1 2016
KCC DODGE CITY

MP

MAR 04 2016
RECEIVED

Form CP-2/3

NO
3-17-16