

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-10073-00-00
Spot: NESW Sec/Twnshp/Rge: 28-21S-41W
1975 feet from S Section Line, 3310 feet from E Section Line
Lease Name: HCU Well #: 2811
County: HAMILTON Total Vertical Depth: 2795 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1300		
PROD	4.5	2795	0	WITH 100 SX CMT
SURF	8.625	109		WITH 150 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/29/2016 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: LEO Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/29/2016 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG IS STUCK IN THE HOLE DUE TO A GLORIETTA CASING LEAK. PRESSURE TEST TBG TO 1000#. HOLDING. (PREVIOUS LEAK IN GLORIETTA FROM 1520' TO 1570' SQUEEZED WITH 80 SX CMT). RUN WIRELINE FREE POINT. TBG STUCK AT 1598' & BELOW & FREE AT 1574'. PERFORATE 4 HOLES THROUGH TBG & CASING AT 2000'. INJECTION RATE 3 BPM @ 50#. PUMP 25 SX CMT, 15 BALL SEALERS THEN 5 SX CMT THROUGH PERFS. DISPLACE TO 1500'. PRESSURE TO 500#. LEFT 250' CMT IN THE TBG & 25 SX CMT OUT THE PERFS. CUT TBG @ 1318' & TOOH. SET CIBP @ 1300'. ATTEMPT TO PRESSURE TEST CASING. WOULD NOT HOLD PRESSURE. PERFORATE 4 HOLES AT 1250'. RUN TBG & PACKER TO 700'. PUMP 80 SX CMT. DISPLACE TO 900' LEAVING 30 SX CMT IN THE CASING & 50 SX CMT OUTSIDE THE CASING. TOOH WITH TBG & PACKER. PERFORATE 4 HOLES AT 350'. CIRCULATE CMT TO SURFACE WITH 95 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:


Top	Bot	Thru	Comments
2758	2774		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

KCC WICHITA

MAR 04 2016

RECEIVED

RECEIVED
MAR - 2 2016
KCC DODGE CITY

Form CP-2/3

NO
3-17-16