

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24016-00-00
Spot: S2N2S2NE Sec/Twnshp/Rge: 14-16S-26W
3522 feet from S Section Line, 1315 feet from E Section Line
Lease Name: EVEL E Well #: 2
County: NESS Total Vertical Depth: 4524 feet

Operator License No.: 4689
Op Name: LUTZ, THOMAS C.
Address: PO BOX 1766
FAYETTEVILLE, AR 72702

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1958		WITH 225 SX CMT
PROD	5.5	4504	0	WITH 150 SX CMT
SURF	8.625	2330		WITH 165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2016 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KENNY RUPP Company: NORTH FOLK WELL SERVICES Phone: (785) 798-2300

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 150# HULLS. PULL TBG TO 2000' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/26/2016 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4350' & SPOT 35 SX CMT & 150# HULLS. PULL TBG TO 2000' & PUMPED 255 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4393	4398		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS & HIGH FL** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier

(TECHNICIAN)
KCC WICHITA

RECEIVED
MAR - 1 2016
KCC DODGE CITY

SA

MAR 04 2016
RECEIVED

Form CP-2/3
203-17-16