

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-20938-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 24-2S-36W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: FRISBIE INC. Well #: 1-24
County: RAWLINS Total Vertical Depth: 5038 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5032		450 SX
SURF	8.625	357		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2016 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 269-7290

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 700 # gel and 500 # hulls.
8 5/8" surface casing set at 357' w/350 sx cement.
5 1/2" production casing set at 5032' w/450 sx cement
TD 5038'. PBTD 5008'
Perforations: 4377' - 4384', 4414' - 4420'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2016 1:05 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4817' and pumped 700 # gel followed by 80 sx cement w/400 # hulls. Pulled tubing to 3195' and pumped 155 sx cement. Pulled tubing to 1600' and pumped 145 sx cement. CWC. Pulled tubing to surface. Connected to 5 1/2" casing and pumped 20 sx cement. Connected to 8 5/8" surface casing and pumped 10 sx cement. Pressured to 350 psi.

GPS: 39.87125N -101.31537W

Perfs:

Top	Bot	Thru	Comments
4414	4420		
4377	4384		

Remarks: CONSOLIDATED OILWELL SERVICES LLC TICKET # 46,631

Plugged through: TBG

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CM

MAR 04 2016

KCC WICHITA

MAR 11 2016

RECEIVED

Form CP-2/3

No
3-17-16