

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-109-20935-00-00  
Spot: SWNENWNE Sec/Twnshp/Rge: 1-12S-33W  
458 feet from N Section Line, 1950 feet from E Section Line  
Lease Name: WEBER TRUST Well #: 1-1  
County: LOGAN Total Vertical Depth: 4700 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4698		170 SX
SURF	8.625	222		165 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/24/2016 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 269-7290

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 800 # gel and 400 # hulls.  
8 5/8" surface casing set at 222' w/165 sx cement.  
5 1/2" production casing set at 4698' w/170 sx cement. TOC 3670'.  
TD 4700'. PBTD 4672'.  
CIBP set at 4440' w/2 sx cement on top.  
Perforations: 4104' - 4606'.  
Port Collar set at 2592' w/260 sx cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 02/24/2016 12:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4100' and pumped 800 sx gel followed by 80 sx cement w/400 # hulls. Pulled tubing to 2600' and pumped 130 sx cement. Pulled tubing to 1300' and pumped 130 sx cement. CWC. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 20 sx cement. Casing full. Connected to 8 5/8" surface casing and pumped 20 sx cement. Pressured to 300 psi.

Perfs:

Top	Bot	Thru	Comments
4596	4606		JOHNS ZN
4462	4467		PAWNEE
4272	4274		LKC 'K'
4265	4268		LKC 'K'
4240	4245		LKC 'J'
4218	4228		LKC 'I'
4187	4193		LKC 'H'

Remarks: HURRICANE SERVICES TICKET # 100,625. PLUG COMPLETE. PLUG NOT WITNESSED.

Plugged through: TBG

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CR

MAR 04 2016

KCC WICHITA

MAR 11 2016

RECEIVED

Form CP-2/3  
710  
3-17-16