

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22247-00-00
Spot: NENWNESW Sec/Twnshp/Rge: 21-15S-22W
2750 feet from N Section Line, 1760 feet from W Section Line
Lease Name: JUNE Well #: 2
County: TREGO Total Vertical Depth: 4214 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4207		300 SX
SURF	8.625	219		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2016 10:30 AM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Rcvd. from: ARNOLD HESS Company: HESS OIL COMPANY Phone: (785) 731-5615

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 300 # hulls and 18 sx gel.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2016 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 4190' and pumped 18 sx gel followed by 75 sx cement w/100 # hulls. Pulled tubing to 1685' and pumped 175 sx cement. Circulated cement to the pit. POOH. Hooked to braden head and pumped 5 sx cement at 350 psi. Topped off casing w/25 sx cement. Casing standing full.
03/02/2016- Cement 70' - 75' down.

Perfs:

Top	Bot	Thru	Comments
4207	4214		

Remarks: SWIFT CEMENTING AND ACID TICKET # 29106

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
(TECHNICIAN)
KCC WICHITA

cm

MAR 07 2016

MAR 11 2016
RECEIVED

Form CP-2/3
no
3-17-16