


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Kingman County, Sec. 31 Twp. 27 Rge. 8 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NE NW
Lease Owner Wentworth & Sons
Lease Name McClure Well No. 1
Office Address 910 Palace Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 28 1951
Application for plugging filed August 28 1951
Application for plugging approved August 28 1951
Plugging commenced August 28 1951
Plugging completed August 28 1951
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation None Depth to top Bottom Total Depth of Well 4545 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	238'	None
				5 1/2"	3845'	3240'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole back to 3750' with sand and rock. Dumped 6 sacks cement with dump bailer. Filled hole with Rotary Drilling mud. Bridged hole at 220 feet and dumped 15 sacks cement with dump bailer. Filled hole with mud to 15 feet below surface and dumped 5 sacks cement, by hand.

9-26-51



(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Wentworth & Sons
Address 910 Palace Building, Tulsa, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

 (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wesley G. Wentworth
Wesley G. Wentworth
910 Palace Building, Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 1951
 Notary Public.

My commission expires 12-20-54
22-7377-s 4-49-10M
FRI 21 27 80
107-34

DRILLERS LOG

Wentworth & Sons - McClure Well No. 1
 Located in the NW NE Section 31-27-8W
 Kingman County, Kansas

Elevation: 1623'
 Commenced: July 26, 1951
 Completed: August 29, 1951

<u>FEET</u>		
From	To	
0	117	Sand
117	460	Red bed
460	490	Shale
490	600	Red Bed
600	1300	Shale and shells
1300	1570	Shale and lime
1570	1630	Sandy shale
1630	1712	Sandy Lime
1712	2820	Lime and shale
2820	3125	Lime
3125	3285	Lime and shale
3285	3311	Sandy shale
3311	3347	Lime
3347	3365	Sandy shale
3365	3374	Shale
3374	3834	Lime
3834	3870	Lime and shale
3870	4018	Lime
4018	4065	Chat
4065	4093	Lime
4093	4180	Lime and shale
4180	4210	Lime
4210	4306	Shale
4306	4330	Shale and lime
4330	4358	Lime and chat
4358	4379	Lime
4379	4450	Shale and lime
4450	4476	Sancy shale
4476	4491	Lime and shale
4491	4545	Lime - T. D.

PLUGGING
 FILE SAC 31 T 22 R 8W
 BOOK PAGE 107 LINE 34

5-21-52
RECEIVED
 STATE CORPORATION COMMISSION

MAY 21 1952

CONSERVATION DIVISION
 Wichita, Kansas