


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 24 Twp. 27 Rge. 8W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SW SW

Lease Owner Mack Oil Company
Lease Name Freeland #1 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/31/78 _____ 19____
Plugging completed 2/4/78 _____ 19____
Reason for abandonment of well or producing formation
depleted. _____

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4452
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	253	none
				4 1/2"	4117	3322'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Pushed wood plug to 3950' and sanded to 3925', ran 4 sacks cement. Loaded hole
with salt water, shot pipe at 3322' and pulled 82 joints. Halliburton pumped 3 sacks
hulls, 20 sacks gel, released plug and pumped 100 sacks 50-50 pos with 2% gel and 3% cc.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1978

2-13-78

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KEISO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of Feb., 1978

Margaret Melcher
Notary Public.

My commission expires



15-095-20638-0000

COMPANY: Mack Oil Co.

SEC. 24 T. 27S R. 8W

WELL NAME: Freeland #1

LOC. C SW SW

COUNTY: Kingman

RIG NO. #7

TOTAL DEPTH 4452'

ELEVATION

COMMENCED: 10-5-77

COMPLETED: 10-18-77

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 253' w/200 sx. common, 2% gel, 3% cc.

PRODUCTION: 4 1/2" @ 4117' w/25 sx. 60/40 poz., 10% salt, 3/4 of 1% CFR and 125 sx. common, 18% salt, 3/4 of 1% CFR2.

LOG

(Figures Indicate Bottom of Formations)

Sand & Shale	210
Shale	1545
Shale & Lime	2010
Shale	2329
Shale & Lime	2580
Shale	2765
Shale & Lime	3335
Lime	4452
<u>ROTARY TOTAL DEPTH</u>	<u>4452</u>

RECEIVED
STATE CORPORATION COMMISSION

JAN 09 1978 1-9-78

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the Freeland #1 well.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me this 20 day of October, 1977.

My Appointment Expires:
10-4-79

Juanita M. Green
Juanita M. Green