


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 7 Twp. 27S Rge. 8 XXX (W)

Location as "NE/CNW/SW" or footage from lines C SE SW
Lease Owner Natural Gas and Oil Company
Lease Name Sample Well No. 1
Office Address P. O. Box 105 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 21 19 60
Application for plugging filed 8-21-60 Verbal August 22 19 60
Application for plugging approved Verbal - August 21 19 60
Plugging commenced August 21 19 60
Plugging completed August 21 19 60
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel - Pretty Prairie, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4410 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	319	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 300'
Set plug and 1/4 sack hulls, 15 sacks cement thru drill pipe
Mud to 35'
Plug and 1/4 sack hulls, 10 sacks cement
2 sacks dry cement in rat hole.
Plugging completed 11:45 p.m. 8-21-60.

8-23-60

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

I, J. B. Steele, Jr. (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Steele, Jr.
F. O. Box 105 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 19 60

My commission expires August 1, 1964

Notary Public.

DRILLERS LOG

CASING RECORD: 319.5' new 8-5/8" surface casing
 COMPANY: Natural Gas & Oil Co.
 CONTRACTOR: Strata Drilling, Inc.
 DESCRIPTION: SE SW Section 7-27S-8W Kingman County, Kansas
 TOTAL DEPTH: 4410'
 COMMENCED: August 10, 1960
 COMPLETED: August 21, 1960

D. & A.

FORMATION	FROM	TO	REMARKS
Surface Clay	0	40	Ran 8 joints of new 8-5/8" surface casing; set and cemented at 319.5' with 225 sacks of common cement with HAS plug down @ 12:20 A. M. 8-11-60.
Sand & Shale	40	140	
Red Bed & Shale	140	320	
Shale & Shells	320	1400	
Shale & Lime	1400	1740	
Lime	1740	1930	
Shale & Lime	1930	2893	
Lime	2893	3066	
Lime & Shale	3066	3205	
Sand & Shale	3205	3375	
Lime	3375	3824	DST #1 4309'-4317' Tool open 1 hr. Recovered 280' of salt water, weak blow. IHMP 2279 lbs. ISP 1447 lbs. IFP 22 lbs. FFP 134 lbs. FSP 1425 lbs. in 20 minutes.
Lime & Shale	3824	4042	
Cherty Lime	4042	4070	
Lime	4070	4177	
Shale & Lime	4177	4308	
Viola	4308	4371	
Lime	4371	4384	
Sand	4384	4410	

Total Depth 4410'

Ran Schlumberger Log.

D. & A. Plugged with rotary mud to 300'. Plugged with 15 sacks of cement and 1/4 sack of hulls, to 35'; plugged with 10 sacks of common cement and 1/4 sack of hulls. Job completed at 11:45 P. M. 8-21-1960.

8-25-60

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1960

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Jim B. McWilliams
Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 23rd day of August, 1960.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

My Commission Expires:
December 14, 1961