


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 6 Twp. 27 Rge. 8 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines. NE NE NE
Lease Owner Harvey Rosen
Lease Name Lizzy Keller Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 8-7-63 19
Plugging completed 8-9-63 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 4502 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	223'	None
				5-1/2"	4470'	3478'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

11-12-63

Checked hole to 4500', sanded to 4460' and dumped 5 sacks of cement @ 4460' with dump bailer. Pulled 5 1/2" casing, checked fluid to 170', bailed fluid to 250', set rock bridge to 240' and ran 25 sacks of cement @ 240'. Mudded to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1963

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of August, 1963

Milton J. Volin

Notary Public.

My commission expires May 20, 1964

Harvey Rosten
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas 15-095-00459-0000

Company- J. B. COLLINS, ETAL
Farm- Lizzy Keller No. 1

SEC. 6 T. 27 R 8W
NE NE NE

Total Depth. 4502'

Comm. 5-18-62

Comp. 6-21-62


Shot or Treated.

Contractor. S & S Drilling.

Issued. 9-22-62

County Kingman

KANSAS



Elevation. 1692' KB

Production. Dry

CASING:
8" 223' cem w/125 sz.
5" 4470'

Figures Indicate Bottom of Formations.

surface soil & sand	80
red bed & shale	180
shale	205
red bed & shale	1315
Fort Riley lime	1610
lime & shale	2585
shale	2720
lime & shale	3425
lime	3470
lime & shale	3559
lime	3798
lime & shale	4007
lime	4094
lime & shale	4303
lime	4380
lime & shale	4466
lime	4502
Total Depth	

TOPS: LOG	
Hegbner	3168
Brown Lime	3361
Kansas City	3376
Mississippi	3596
Kinderhook	4104
Viola	4298
Simpson Sand	4372
Arbuckle	4466

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1963

8-8-63

CONSERVATION DIVISION
Wichita, Kansas