

15-095-00435-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 6 Twp. 27 Rge. 9W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner Sierra Petroleum Co., Inc.

Lease Name SAYLOR Well No. 1

Office Address 208 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed 8/10/58 19

Application for plugging filed 10/15/58 19

Application for plugging approved 10/17/58 19

Plugging commenced 10/24/58 19

Plugging completed 10/27/58 19

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 10/10/58 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation Depth to top Bottom Total Depth of Well 4223 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	233'	none
				5 1/2	4229'	3385' 47"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Bailed fluid and mudded hole to 250'. Set 10' rock bridge with 20 sacks cement.
Mud to 40' 10' rock bridge and 10 sacks cement to base of ceblar.

11-8-58

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1958

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
S. P. Hall (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. P. Hall

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of November, 1958

Margie Cooper
Notary Public.

My commission expires 1-30-61.

PLUGGING
FILE SEC. 6 T. 27 R. 9W
BOOK PAGE 136 LINE 38

Sierra Petroleum Co., Inc. - Operator

SAYLOR #1

NE NE NE Sec. 6-27S-9W
Kingman County, Kansas

Total Depth: 4230'

Elev: 1727 KB

Comm: 7/25/58

Comp: 8/10/58

Casings:

8 5/8" @ 233'

5 1/2" @ 4229

Cement:

with 225 sacks

with 150 sacks

FORMATION

DEPTH

Sand & shells	120
Shale & sand	190
Red bed	221
Shale	223
Red Bed & shale	618
Shale	1050
Salt, shale	1175
Shale	1440
Anhydrite, lime	1500
Lime & shale	2920
Lime	3004
Lime & shale	3300
Lime, shale & sand	3392
Shale	3415
Lime & shale	3505
Lime	3597
Lime & shale	3649
Lime	3709
Lime & shale	3778
Lime	3830
Lime & shale	3960
Chert & shale	3975
Chert	3993
Chert & lime	4033
Shale	4210
Viola	4230

Tops: Anhydrite	1440
Topeka	2865
Heebner	3232
Douglas	3287
Brown Lime	3404
Lansing K. C.	3415
Mississippi	3949
Kinderhook	4033
Viola	4211

10-16-58

STATE OF KANSAS)
) 681
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Souder

Subscribed and sworn to before me this 11th day of August, 1958.

Margie Cooper
Notary Public

My commission expires: 1-30-61,

PLUGGING	
FILE SEC	6 T 27 R 9W
BOOK PAGE	136 LINE 38