

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Kingman County, Sec. 36 Twp. 27S Rge. (E) 8W (W)
Location as "NE/CNW&SW" or footage from lines. C SW NE

Lease Owner Hall-Jones Oil Corp.
Lease Name Leonard & Opal Well No. 1
Office Address 1704 Liberty Bank Bldg., Okla. City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-25 1971
Application for plugging filed 11-25 1971
Application for plugging approved 11-25 1971
Plugging commenced 11-25 1971
Plugging completed 11-25 1971
Reason for abandonment of well or producing formation z No commercial quantities of oil or gas encountered.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4065 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	208'	8-5/8"	199'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 180', 1/2 sx hulls, plug; 25 sx cement;
Fluid to 40', 1/2 sx hulls, plug; 10 sx cement;
Two sacks cement in rat hole.

Reed
11-29-71

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
Address 737 First National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF _____, ss.
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *James L. Donelson*
737 First Nat'l Bk Bldg., Wichita, Ks.
(Address)

Subscribed and sworn to before me this 26th day of November, 1971

Ella Priess
Ella Priess
Notary Public.

My commission expires August 25, 1972



DRILLERS' LOG

HALL-JONES OIL CORP.
No. 1 Leonard & Opa
C SW NE, Sec. 36-27S-8W
Kingman County, Kansas

Elev: 1599 R.B.

Commenced: 11-18-71
Completed: 11-25-71

Surface Casing: 199' of
8-5/8" cemented w/225 sx
cement, 3% cc. 11-18-71

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	208
Shale & Lime	595
Shale	1100
Lime & Shale	1533
Shale & Lime	1808
Lime & Shale	2405
Shale & Lime	2870
Sand, Lime & Shale	3058
Shale & Lime	3286
Lime	3812
Lime & Shale	4030
Cherty Lime	4065 T.D.

11-29-71
RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1971
CONSERVATION DIVISION
Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 26th day of November, 1971.

My Commission Expires:
August 25, 1972

Ella Priess
Ella Priess, Notary Public

