


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above Section Flat

Kingman County. Sec. 33 Twp. 27S Rge. 9W (X) (W)
Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner Ferguson Oil Company
Lease Name Sears Well No. 1
Office Address 427 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed March 15, 19 61
Application for plugging filed March 15, 19 61
Application for plugging approved March 15, 19 61
Plugging commenced March 15, 19 61
Plugging completed March 15, 19 61
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	248'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 240'. Set bottom plug with 1/4 sx hulls and 15 sx cement. Set top plug at 35' with 1/2 sx hulls and 10 sx cement. Bridged rat hole with 2 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address Box 173 - Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
George A. Angle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle
580 Fourth Nat'l Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of March, 1961

My commission expires 11-17-62
Wesley Head Notary Public.



15-095-00051-0000

DRILLERS LOG

No. 1 Sears

CASING RECORD: 8 5/8" @ 248' w/175 sx
 COMPANY: Ferguson Oil Company
 CONTRACTOR: Red Tiger Drilling Co.
 COMMENCED: March 4, 1961
 COMPLETED: March 15, 1961
 DESCRIPTION: C SE SE
 33-27S-9W
 Kingman County
 Kansas
 ELEVATION: 1636 DE
 1639 RE
 TOTAL DEPTH: 4425'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Clay	0	40	
Shale & Red Rock	40	250	
Red Rock	250	350	
Shale & Shells	350	1135	
Shale	1135	1290	
Lime & Shale	1290	2395	
Lime	2395	2565	
Lime & Shale	2565	3555	
Lime	3555	3625	
Lime & Shale	3625	4019	
Chert & Lime	4019	4034	
Mississippi Lime	4034	4070	
Lime	4070	4115	
Shale	4115	4310	
Chert & Lime	4310	4345	
Lime, Shale & Chert	4345	4425	

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 23 1961
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle
 George A. Angle

Subscribed and sworn to before me this 16th day of March, 1961.

Notary Seal
 Notary Public

My Commission Expires:
11-17-62