


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 21 Twp. 27S Rge. 9 (W)

Location as "NE/CNW/SW" or footage from lines C SE NE  
Lease Owner John C. Graves, et al  
Lease Name Garibay Well No. 1  
Office Address 505 Union Center, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 13, 19 68  
Application for plugging filed May 13, 19 68  
Application for plugging approved May 13, 19 68  
Plugging commenced May 13, 19 68  
Plugging completed May 13, 19 68  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Warren, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4268 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	220'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 210 feet. Followed by wooden plug and 1/4 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/4 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.  
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *John C. Graves*  
505 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of May, 19 68

*Betty Brandt*  
Betty Brandt Notary Public.

My commission expires May 9, 1971

ROTARY DRILLERS' LOG

OPERATOR: John C. Graves, et al DRILLING COMMENCED: May 5, 1968  
 505 Union Center  
 Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: May 13, 1968  
 505 Union Center  
 Wichita, Kansas

CASING RECORD: 10 Jts. 220' 8-5/8" LOCATION: Garibay No. 1  
 cemented with 175 sacks C SE NE  
 Section 21-27S-9W  
 Kingman County, Kansas

-----


0 - 90	Sod & sand
90 - 390	Red bed
390 - 1310	Shale & shells
1310 - 1571	Shale with lime streaks
1571 - 2481	Lime & shale
2481 - 2550	Shale & lime
2550 - 2815	Lime & shale
2815 - 3117	Lime
3117 - 3285	Lime & shale
3285 - 3410	Shale & sand
3410 - 3856	Lime
3856 - 3990	Lime & shale
3990 - 4005	Lime
4005 - 4016	Chert & lime
4016 - 4029	Chert
4029 - 4038	Lime
4038 - 4048	Lime & chert
4048 - 4251	Shale
4251 - 4268	Lime
4268	Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 22 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John C. Graves  
President



)  
)  
) ss:

Subscribed and sworn to before me, a Notary Public, this 21st of May, 1968.

My commission expires: May 9, 1971

Betty Brandt  
Betty Brandt Notary Public