

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 15-095-21701 0000

LEASE NAME Steffen

WELL NUMBER #1

660' Ft. from S Section Line

4620' Ft. from E Section Line

SEC. 18 TWP. 27S RGE. 10W (E) or (W)

COUNTY Kingman

Date Well Completed 1-21-95

Plugging Commenced 10-08-98

Plugging Completed 10-08-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR MTM Petroleum, Inc.

ADDRESS PO Box 82 Spivey KS 67142

PHONE (616) 532-3794 OPERATORS LICENSE NO. 6236

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-05-98 (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Miss. Depth to Top 4004' Bottom T.D. 4294'

Show depth and thickness of all water, oil and gas formations. 10-29-98

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	282'	None
				5 1/2	4127'	2720'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from ___ feet to ___ feet each s
Set bridge plug @ 3900'; spot in 5 sks cement; pull pipe back to 1486' spotted 35 sks cement; pulled pipe back to 950'; spotted 35 sks cement; pulled remaining pipe; cemented surface with 90 sks cement from 330' to surface; topped off with 15 sks. Used total of 175 sks 60/40 Pozmix with 4% gel

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address PO Box 333 Attica KS 67009

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Marvin A. Miller, MTM Petroleum, Inc.

STATE OF Kansas COUNTY OF Kingman, ss.

Marvin A. Miller, President MTM Petroleum, Inc (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed i the same are true and correct, so help me God.

 KATHY HILL
Notary Public - State of Kansas
My Appt. Expires 01-04-99

(Signature) [Signature]

(Address) Marvin A. Miller, President
PO Box 82 Spivey KS 67142

SUBSCRIBED AND SWORN TO before me this 28th day of October, 1998

Kathy Hill
Notary Public
Kathy Hill

My Commission Expires: 01-04-99

USE ONLY ONE SIDE OF EACH FORM