


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Kingman County, Sec. 9 Twp. 27S Rge. 9 (W)  
Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Cooperative Refinery Association  
Lease Name VALDOIS Well No. #1  
Office Address 405 E. 13th St., Kansas City, Missouri  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed August 24, 1956 19 56  
Application for plugging filed August 24, 1956 (by phone) 19 56  
Application for plugging approved August 24, 1956 19 56  
Plugging commenced August 24, 1956 19 56  
Plugging completed August 24, 1956 19  
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 4440' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 300' 1/3 Sacks Hulls  
HOWCO Plug at 300'  
20 Sacks cement

Mud to 35' 1/3 sacks Hulls  
HOWCO Plug at 35'  
10 sacks cement

Job completed at 12:00 noon

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Stearns Petroleum, Inc.  
Address Box 313, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
D. D. Stewart (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. D. D. Stewart

(Signature) *D. D. Stewart*  
Box 313, Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 25th day of August, 19 56

My commission expires April 5, 1958

*Betty Lou Miller*  
Betty Lou Miller Notary Public.

PLUGGING  
FILE SEC. 9 T27 R9W  
BOOK PAGE 93 LINE 12

RECEIVED  
AUG 27 1956  
CONSERVATION DIVISION  
Wichita, Kansas

VALDOIS #1

Operator: Cooperative Refinery Association  
 Contractor: Stearns Petroleum, Inc.  
 Commencement Date: July 30, 1956  
 Completion Date: August 24, 1956  
 Elevation: 1724' K. B.  
 I.P.: D & A

Location  
 SE SE SW  
 Section 9-27S-9W  
 Kingman County, Kansas

Surface Casing: 17 joints of 8-5/8" casing set at 355'. Cemented with 225 sacks Pozmix and 1 sack Calcium Chloride.

WELL LOG

Shale & Sand	0	185
Red Bed	185	355
Sand, Shale & Gyp	355	500
Shale & Shells	500	715
Sand, Shale & Shells	715	1415
Shale & Shells	1415	1630
Shale & Lime	1630	3000
Lime	3000	3075
Lime & Shale	3075	3130
Lime	3130	3860
Lime & Shale	3860	3890
Lime	3890	3930
Lime & Shale	3930	3990
Cherty Lime	3990	4048
Shale, Lime, Chert	4048	4087
Shale	4087	4133
Shale & Lime	4133	4243
Cherty Lime	4243	4300
Lime	4300	4318
Sandy Shale & Cherty Lime	4318	4339
Lime	4339	4365
Shale	4365	4385
Lime & Shale	4385	4423
Lime	4423	4440
R.T.D.	4440	

Tops:

Heebner Shale	3232	(-1508)
Douglas	3252	(-1528)
Brown Lime	3432	(-1708)
Lansing Kansas City	3445	(-1721)
Mississippi	3969	(-2255)
Kinderhook Shale	4046	(-2322)
Kinderhook Lime	4236	(-2512)
Misener Sand	4242	(-2518)
Viola	4243	(-2519)
Simpson Shale	4321	(-2597)
Arbuckle	4416	(-2692)

STATE OF KANSAS )  
 )  
 COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

STEARNS PETROLEUM, INC.

*O. G. Stearns*  
 O. G. Stearns, President

SUBSCRIBED AND SWORN TO BEFORE ME, a Notary Public, this 30th day of August, 1956.

RECEIVED  
 SEP 4 1956  
 CONSERVATION DIVISION

My Commission Expires: April 15, 1958

*Betty Lou Miller*  
 Betty Lou Miller, Notary Public

PLUGGING  
 FILE SEC. 9 T. 27 R. 9W  
 BOOK PAGE 93 LINE 12