

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21426-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 29-7S-17W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: KRILEY A Well #: 2
County: ROOKS Total Vertical Depth: 3290 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3250		150 SX
SURF	8.625	1202		450 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2016 12:30 PM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Rcvd. from: JOHN LOWRY Company: HESS OIL COMPANY Phone: (785) 303-0779

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement, 10 sx gel and 500 # hulls.
02/24/2016- Operator had RGN Co. pressure up on annulus to 300 psi.
Production perforations: 3050' - 3250'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2016 2:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3027' and pumped 10 sx gel followed by 50 sx cement w/300 # hulls. Pulled tubing to 1752' and pumped 200 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pressured to 300 psi immediately.

GPS: 39.42129N -099.24873W

Perfs:

Top	Bot	Thru	Comments
3050	3250		

Remarks: SWIFT SERVICES TICKET # 28769

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

KCC WICHITA

MAR 11 2016

RECEIVED

MAR 07 2016

Form CP-2/3

NO
3-17-16