

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-26820-00-00  
Spot: SENWSENE Sec/Twnshp/Rge: 29-13S-19W  
1868 feet from N Section Line, 788 feet from E Section Line  
Lease Name: BEMIS Well #: 1-29  
County: ELLIS Total Vertical Depth: 3920 feet

Operator License No.: 35287

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.765	219		160 sx

Op Name: FLATLAND RESOURCES CORPORATIO

Address: PO BOX 763  
HAYS, KS 67601

Well Type: DH

UIC Docket No:

Date/Time to Plug: 02/08/2016 12:00 AM

Plug Co. License No.: 31548

Plug Co. Name: DISCOVERY DRILLING

Proposal Rcvd. from: TOM

Company: DISCOVERY DRILLING

Phone: (785) 623-2920

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL

Witness Type: NONE

Date/Time Plugging Completed: 02/08/2016 9:15 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

1st plug @3815 w/50 sx  
2nd plug @1510 w/50 sx  
3rd plug @755 w/100 sx  
4th plug @270 w/50 sx  
5th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Remarks: SWIFT

Plugged through: DP

District: 04

Signed

*Ray A. Dinkel*

(TECHNICIAN)

cm

KCC WICHITA

MAR 09 2016

RECEIVED

MAR 8 1 2016

Form CP-2/3

*NO 3-17-16*