

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-21175-00-00
Spot: NW Sec/Twnshp/Rge: 11-1S-33W
915 feet from N Section Line, 1635 feet from W Section Line
Lease Name: MARJORIE-NORMA JEAN UNI Well #: 1-11
County: RAWLINS Total Vertical Depth: 4124 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	221		150 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/12/2016 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: NONE
Date/Time Plugging Completed: 02/12/2016 8:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report: _____ Perfs: _____

1st plug @2750 w/50 sx
2nd plug @2000 w/100 sx
3rd plug @275 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: ALLIED
Plugged through: DP

District: 04

Signed Darrel Dipman

(TECHNICIAN)
KCC WICHITA

CM

MAR 09 2016

RECEIVED

Form CP-2/3

70
3-17-16

MAR 01 2016