

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-01975-00-01
Spot: SESENE SW Sec/Twnshp/Rge: 6-24S-14E
1495 feet from S Section Line, 2890 feet from E Section Line
Lease Name: WINTERSCHIED Well #: 17
County: WOODSON Total Vertical Depth: 1717 feet

Operator License No.: 34827
Op Name: C3OIL, LLC
Address: 600 ARROWHEAD DR
NEW STRAWN, KS 66839

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1717		
PKR		1630		PACKER TYPE AND SETTING DEPTH: BAKER SET @ 1630'
PROD	6.375	1637		125 SX
PROD	8.25	1650		
SURF	10	39		
SURF	8.25	1650		125 SX
T1	2.875	1650		

Well Type: EOR UIC Docket No: E26973.2 Date/Time to Plug: 02/19/2016 9:00 AM
Plug Co. License No.: 33413 Plug Co. Name: TITUS WELL SERVICE LLC
Proposal Rcvd. from: CHRIS HAAS Company: Phone: (913) 515-5329

Proposed Plugging Method: Since the 2 3/8 fiberglass is cemented to the top there is no need to perf this well. 1" will be run to bottom by contractor and cement will be circulated to the top until well is plugged.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 02/19/2016 12:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran 1" to 1652' pumped 20 sxs cement, pulled 1" to 826' pumped 15 sxs cement to surface, pulled 1" out topped well off.

Perfs:

Top	Bot	Thru	Comments
1678	1717		
RECEIVED KCC DIST # 3 MAR 07 2016 CHANUTE, KS MH			

Received
KANSAS CORPORATION COMMISSION

Remarks:

MAR 10 2016

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 03

Signed Miko Heffern
(TECHNICIAN)

no
3-17-16
cc-llc

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. 2727
 Foreman Steve Mead
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
2-19-16	1021	Winterscheid #17	6	24	14E	Woodson	Ks	
Customer C-3011			Safety Meeting		Unit #	Driver	Unit #	Driver
Mailing Address 600 Arrowhead Drive					102	Rick		
					112	Allen B		
					145	Russ		
City New Strawn		State Ks	Zip Code 66839					

Job Type PTA Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8 1652'
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. _____ Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Rig up to 1" Tubing. Wash 1" down to 1652'. Circulate well clean. Mix 20 sks 60/40 permix 4% Gel. Pull out 25 joints Tubing. Mix 15 sks 826 to surface. Pull out all 1" Mix 5 sks cement. Shut well in at 300#. Job complete Rig down

Thank you

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	30	Mileage	3.95	118.50
C203	40 sks	60/40 Permox Cement	12.75	510.00
C206	135 #	Gel 4%	.20	27.00
C108A	1.73 Ton	Ton mileage bulk Truck	MISC	345.00
C113	3 hrs	80 bbl Gas Truck	85.00	255.00
C224	3000 gal/hr	CITY WATER	10.00 per 1000	30.00
C116		1" Rental	100.00	100.00
Received KANSAS CORPORATION COMMISSION MAR 10 2016 CONSERVATION DIVISION WICHITA, KS				
			Sub Total	2135.50
			7.50% Sales Tax	160.16
Authorization _____ Title _____			Total	2295.66

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.