

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-03902-00-00
Spot: SESENE SW Sec/Twnshp/Rge: 16-24S-18E
1382 feet from S Section Line, 2651 feet from E Section Line
Lease Name: FLEWHARTY Well #: OW-1
County: ALLEN Total Vertical Depth: 868 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	0	0		0 SX
SURF	8	24		0 SX
SURF	9.5	40		

Well Type: _____ UIC Docket No: _____ Date/Time to Plug: 02/26/2016 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: COLT ENERGY, INC. Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: OLD WELL WASHED DOWNDROP 2 3/8" TUBING DOWN TO TD - GEL HOLE - CEMENT 100' AT TD, CEMENT 50' AT 500', CEMENT @ 250' TO SURFACE.

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 02/26/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 2" tubing to 868'. Mixed and pumped gel at TD. Pumped and placed 150' cement plug at TD. Pulled up to 500'. Pumped and placed 50' plug at 500'. Pulled 2" tubing to 250'. Pumped and circulated cement from 250' to surface. Pulled 2" tubing from hole and topped the well off with cement. A total of 139 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1	2		

RECEIVED
KCC DIST #3
MAR 09 2016
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

District: 03

Signed [Signature] E.C.R.S.
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
MAR 14 2016
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3
NO
3-17-16