

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-21563-00-01
Spot: NESESWNW Sec/Twnshp/Rge: 22-32S-21W
2090 feet from N Section Line, 1233 feet from W Section Line
Lease Name: STEPHENS Well #: 10
County: CLARK Total Vertical Depth: 6760 feet

Operator License No.: 31691
Op Name: CORAL COAST PETROLEUM, L.C.
Address: 8100 E 22ND ST N BLDG 600, STE R
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5234		WITH 3 SX CMT
CIBP		6380		
PROD	5.5	6622	2500	WITH 335 SX CMT
SURF	8.625	605		WITH 200 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/11/2015 8:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: DAVID PAULY Company: CORAL COAST Phone: (316) 250-2045

Proposed Plugging Method: Set CIBP @ 5250' spot 3 sx. cement on plug. Pull 5.5" casing whic is set @ 6,600' with 175 sx.. Run tubing to 1070' Cement to surface. Pump 50 sx. down braden head (surface casing)

Plugging Proposal Received By: WADE KLAUS WitnessType: NONE
Date/Time Plugging Completed: 09/11/2015 10:45 AM KCC Agent: WADE KLAUS

Actual Plugging Report:

SET CIBP @ 5234' WITH 3 SX CMT. CUT CASING AT 4150'. COULD NOT PULL. SHOT OFF AT 2500'. PULLED CASING. 1ST PLUG AT 1165' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 842' WITH 50 SX CMT. 3RD PLUG AT 226' WITH 50 SX CMT. 4TH PLUG AT 65' WITH 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
6416	6428		
5284	5290		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
FEB 29 2016
KCC DODGE CITY

Signed BWB
SA
KCC WICHITA (TECHNICIAN)
MAR 11 2016
RECEIVED

700 Form CP-2/3
3-17-16