

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22729-00-00
Spot: N2NENENE Sec/Twnshp/Rge: 4-11S-23W
90 feet from N Section Line, 330 feet from E Section Line
Lease Name: MCCALL 4-1 Well #: #1
County: TREGO Total Vertical Depth: 4090 feet

Operator License No.: 31819
Op Name: CHOLLA PRODUCTION, LLC
Address: 10390 BRADFORD RD. SUITE 201
LITTLETON, CO 80127

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4079		275 SX
SURF	8.625	262		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/03/2016 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: KELLY BRANUM Company: CHOLLA PRODUCTION, LLC Phone: (785) 324-1414

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/200 # hulls.
Port Collar at 1796' w/245 sx cement.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/03/2016 12:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 4030' and pumped 100 sx cement. Pulled tubing to 2535' and pumped 100 sx cement. Pulled tubing to 1040' and pumped 75 sx cement. Circulated cement to pit. POOH. Topped off casing w/15 sx cement. Casing standing full. Dug braden head out and found to be full of cement.

GPS: 39.13192 -099.87074

Perfs:

Top	Bot	Thru	Comments
3660	3664		
3608	3611		

Remarks: QUALITY CEMENTING TICKET # 1326

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

KCC WICHITA

MAR 11 2016

RECEIVED

MAR 07 2016

Form CP-2/3

NO
3-17-16