

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-147-20712-00-00
Spot: E2NESWNW Sec/Twnshp/Rge: 3-2S-19W
1650 feet from N Section Line, 1000 feet from W Section Line
Lease Name: BILLY Well #: 2
County: PHILLIPS Total Vertical Depth: 3695 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3695		600 SX
SURF	8.625	217		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/03/2016 12:00 PM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 11 sx gel and 300 # hulls.
Production perforations: 3426' - 3599'

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/03/2016 3:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 75 sx cement w/300 # hulls followed by 11 sx gel.
Pumped 190 sx cement with a maximum pressure of 1800 psi. Hooked to 8 5/8" x 5 1/2" annulus and pressured to 350 psi immediately.
GPS: 39.91066N -099.45581W

Perfs:

Top	Bot	Thru	Comments
3589	3599		
3515	3519		
3491	3494		
3443	3447		
3426	3429		

Remarks: GLOBAL CEMENTING TICKET # 2550

Plugged through: CSG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

KCC WICHITA

CM

MAR 07 2016

MAR 11 2016

RECEIVED

Form CP-2/3

No 3-17-16